



1 PLUMBING - DOMESTIC WATER FLOOR PLAN 1/4" = 1'-0"



KEY NOTES: (X)

- CONNECT NEW 1/2" CW TO EXISTING CW SERVICE ABOVE CEILING. PLUMBING CONTRACTOR SHALL FIELD VERIFY EXACT LOCATION OF EXISTING WATER SERVICE PRIOR TO THE INITIATION OF ANY WORK. PROVIDE WATER SUB-METER AND REDUCED-PRESSURE BACKFLOW PREVENTOR. ROUTE RELIEF PIPING TO FLOOR DRAIN 3" ED-2
- EXISTING NATURAL GAS SERVICE STUB UP. PLUMBING CONTRACTOR SHALL FIELD VERIFY EXACT LOCATION OF GAS SERVICE PRIOR TO THE INITIATION OF ANY WORK
- NEW GAS METER ASSEMBLY BY LOCAL GAS COMPANY. PLUMBING CONTRACTOR SHALL PROVIDE NEW GAS SERVICE DOWNSTREAM OF METER ASSEMBLY TO ALL EQUIPMENT WITHIN NEW WOODHOUSE SPA. SEE GAS RISER DIAGRAM SHEET P3.0

GENERAL NOTES:

- CONTRACTOR SHALL INVESTIGATE THE AGE AND CONDITION OF ALL PIPING TO REMAIN. IF PIPING CONDITION IS NOT SUITABLE FOR REUSE, THE CONTRACTOR SHALL NOTIFY THE ENGINEER PRIOR TO THE COMMENCEMENT OF WORK.
- FIELD VERIFICATION OF EXISTING PIPING. ALL EXISTING PIPING SHOWN ON THE CONSTRUCTION DOCUMENTS IS BASED OFF OF THE SITE INVESTIGATION AND AS BUILT DRAWINGS OF THE EXISTING SITE AND BUILDING CONSTRUCTION. THE ENGINEER WAS NOT ABLE TO PERFORM ANY SELECTIVE INVESTIGATORY DEMOLITION. THE LICENSED PLUMBING CONTRACTOR SHALL FIELD VERIFY ALL EXISTING PIPING LOCATIONS, TYPES, SIZES, ELEVATIONS AND PIPING INVERTS. NOTIFY ENGINEER IF THE CONDITIONS ARE NOT AS SHOWN ON THE PLANS OR AS STATED IN THE SPECIFICATIONS PRIOR TO THE INITIATION OF WORK. IDENTIFICATION AND VERIFICATION OF EXISTING PIPING TO BE ACCOMPLISHED BY THE FOLLOWING MEANS:
 - MANDATORY DYE TESTING OF ALL EXISTING SANITARY PIPING FOR SYSTEM IDENTIFICATION
 - SNAKE ALL SANITARY PIPING FOR A DISTANCE OF 100' FEET AND REPORT ANY BLOCKAGES
 - TEST WATER PRESSURE TO INSURE MINIMUM PSI MATCHES MOST DEMANDING EQUIPMENT SUPPLIED OR TO BE INSTALLED
 - ALL IDENTIFICATION AND VERIFICATION RESULTS SHALL BE SUBMITTED TO THE A/E FOR REVIEW PRIOR TO THE INITIATION OF WORK.

SEAL: [Signature Area]
ADAM J. BARNY
P.E. #114839

Joseph Lawrence & Co
Space Coastal
Consulting Engineers
317 RIVERGATE BLVD. SUITE 110
COCOA, FLORIDA 32922
TEL 321.972.4466
WWW.JL&C.COM
CA NO. 32770
JLSC19.015.00

NO	DATE	REMARKS

**WOODHOUSE DAY SPA
RENOVATION**
MARKET STREET
9595 SIX PINES DRIVE
THE WOODLANDS, TEXAS 77680

PROJECT NO: 2019.0172
DATE: APRIL 08, 2019

P2.0

CHECKED: LMS DRAWN: PJR

COPYRIGHT © 2019 INTERPLAN, LLC. ALL RIGHTS RESERVED. THESE DOCUMENTS TO THE ORIGINAL SET OR ANY OTHER SET WHICH THEY WERE PREPARED. REPRODUCTION, CHANGES OR ASSIGNMENTS ARE PROHIBITED.